

BILANS ROBÓT ZIEMNYCH - 0ś_Etap III						
Pikleta	Pow. wykopu	Pow. nasypu	Obj. wykopu	Obj. nasypu	Catk. obj. wykopu	Catk. obj. nasypu
9+550.00	1.11	0.45	0.00	0.00	0.00	0.00
9+564.41	1.13	0.29	16.14	5.35	16.14	5.35
9+576.22	1.14	0.45	13.41	4.36	29.55	9.72
9+585.00	1.22	0.59	10.35	4.57	39.90	14.29
9+600.00	1.27	0.15	18.63	5.53	58.53	19.82
9+615.19	1.27	0.27	19.26	3.18	77.79	23.00
9+630.00	1.00	0.53	16.85	5.95	94.64	28.95
9+645.00	1.14	0.35	16.05	6.59	110.69	35.54
9+660.00	1.46	0.24	19.47	4.44	130.16	39.98
9+675.00	1.92	0.04	25.33	2.16	155.49	42.14
9+690.00	1.86	0.03	28.31	0.53	183.79	42.67
9+705.00	1.89	0.00	28.07	0.20	211.86	42.88
9+720.00	1.48	0.09	25.29	0.69	237.15	43.56
9+735.00	1.28	0.17	20.72	1.98	257.87	45.54
9+750.00	1.38	0.22	19.90	2.93	277.77	48.47
9+765.00	1.29	0.21	20.02	3.19	297.78	51.67
9+780.00	1.82	0.05	23.36	1.95	321.14	53.62
9+795.00	1.93	0.02	28.12	0.55	349.26	54.16
9+810.00	1.59	0.32	26.39	2.55	375.65	56.71
9+825.00	2.03	0.11	27.17	3.19	402.82	59.90
9+843.74	2.11	0.05	38.83	1.48	441.65	61.38
9+857.19	1.90	0.04	26.91	0.59	468.56	61.97
9+870.00	2.05	0.05	25.30	0.53	493.86	62.50
9+885.00	1.74	0.07	28.43	0.83	522.29	63.33
9+900.00	1.48	0.16	24.10	1.68	546.39	65.02
9+915.00	1.60	0.08	23.09	1.81	569.48	66.83
9+930.00	1.50	0.21	23.23	2.21	592.70	69.04
9+945.00	1.18	0.26	20.05	3.52	612.76	72.57
9+960.00	1.45	0.14	19.68	2.96	632.44	75.53
9+974.52	1.53	0.14	21.56	2.03	654.01	77.55
9+990.00	1.22	0.20	21.28	2.67	675.28	80.22
10+005.00	1.26	0.22	18.63	3.14	693.91	83.36
10+020.00	1.05	0.31	17.34	3.94	711.25	87.30
10+035.00	1.07	0.32	15.95	4.68	727.20	91.98
10+050.00	1.17	0.40	16.84	5.33	744.04	97.32
10+065.00	0.99	0.64	16.18	7.79	760.22	105.11
10+080.00	0.57	0.99	11.70	12.24	771.92	117.34
10+095.00	0.55	0.79	8.42	13.30	780.34	130.65
10+110.00	0.74	0.79	9.65	11.85	789.99	142.50
10+125.00	1.11	0.69	13.89	11.14	803.88	153.63
10+140.00	1.35	0.45	18.49	8.52	822.37	162.15
10+155.00	1.63	0.07	22.34	3.87	844.70	166.03
10+170.00	1.47	0.06	23.22	0.98	867.92	167.01
10+185.00	1.73	0.02	23.98	0.57	891.90	167.57
10+200.00	0.97	0.45	20.27	3.51	912.17	171.09
10+215.00	1.19	0.37	16.25	6.20	928.42	177.29
10+230.00	1.16	0.31	17.65	5.15	946.07	182.44
10+245.00	1.36	0.48	18.90	5.96	964.97	188.40
10+260.00	1.62	0.52	22.35	7.50	987.32	195.90
10+275.00	1.49	0.56	23.28	8.07	1010.60	203.97
10+290.00	1.34	0.89	21.22	10.84	1031.82	214.80
10+305.00	1.47	0.80	21.08	12.69	1052.90	227.49
10+320.00	1.27	1.24	20.49	15.32	1073.39	242.81
10+335.00	1.28	1.76	19.06	22.49	1092.45	265.30
10+350.00	1.15	1.76	18.17	26.40	1110.62	291.69
10+365.00	0.95	2.23	15.71	29.95	1126.33	321.64
10+380.00	1.33	1.33	17.13	26.73	1143.47	348.37
10+395.00	1.72	1.33	22.88	19.93	1166.35	368.31
10+410.00	0.60	1.41	17.35	20.55	1183.69	388.86
10+425.00	0.49	1.59	8.15	22.55	1191.85	411.41
10+440.00	0.43	2.33	6.93	29.42	1198.77	440.83
10+455.00	0.76	1.56	8.97	29.13	1207.74	469.95
10+470.00	0.59	1.94	10.17	26.25	1217.92	496.20
10+485.00	1.04	0.80	12.23	20.62	1230.14	516.82
10+500.00	1.69	0.34	20.46	8.59	1250.60	525.41
10+515.00	1.56	0.29	24.38	4.74	1274.98	530.15